




Release Candidate Documentation - Contents Subject To Change

OnCommand® System Manager 3.1 RC1

Release Notes

For Data ONTAP® Operating in 7-Mode



NetApp, Inc.
495 East Java Drive
Sunnyvale, CA 94089
U.S.

Telephone: +1 (408) 822-6000
Fax: +1 (408) 822-4501
Support telephone: +1 (888) 463-8277
Web: www.netapp.com
Feedback: doccomments@netapp.com

Part number: 215-08412_A0_ur001
November 2013

Contents

System Manager 3.1 RC1 Release Notes	7
Understanding System Manager	7
Supported versions of Data ONTAP	7
License requirements	8
System requirements for System Manager	8
User interface enhancements	10
Fixed issues	11
Network Interface page stops responding if the /etc/rc file does not contain standard characters	11
Reverse resynchronization fails when a SnapMirror relationship is created using the system IP address	11
Cannot modify SnapLock retention periods simultaneously	12
Incorrect value displayed for volume security style in the Edit Volume window	12
Incorrect Snapshot copy timestamp displayed if daylight saving time is activated	12
Volumes window displays incorrect Snapshot information	12
Configuring network interfaces with static subnet routes generates false alarms	13
System Manager does not reflect the storage system time if daylight saving time is activated	13
Cannot create an aggregate from the Disks page for Data ONTAP-v storage systems	13
Known issues with Data ONTAP	14
Data becomes unavailable if MTU size is not specified in the /etc/rc file	14
Incorrect error message is displayed when disabling thin provisioning in LUNs	14
Cannot change or remove the vFiler unit IP address	14
Known issues and limitations in System Manager	15
Upgrade or installation issues	15
System Manager installation fails with an error message	15
Java script error reported while upgrading System Manager	15
Licensing issues	15
Cannot display the license grace period	16
Storage resource management issues	16

Resizing a LUN might result in data loss	16
LUN Clone field does not display any value	16
SSD disks cannot be added as cache disks from the Disks window	16
System Manager does not perform disk size validation during RAID4 to RAID-DP conversion	16
Spare disk is downsized if the parity disk of a SyncMirror pool is smaller than the spare disk	17
Delay in populating the Flash Cache read workload graph	17
Storage Configuration wizard does not validate disk sizes	17
Cloning a LUN fails if the containing volume is created during the LUN creation operation	18
System Manager does not display online LUNs in an initiator group	18
Incorrect number of spare disks displayed in the dashboard	18
Change in SSD RAID group size is not displayed for Data ONTAP 8.2	18
Mixed RAID types are not supported	19
Incorrect spare disk count reported while mirroring aggregates with disks of different checksum types	19
Aggregates are created by selecting disks from the same carrier without a warning message	19
FCAL disks are incorrectly displayed as SAS disks	19
HA pairs issues	20
HA Configuration window displays timed-out error message during a giveback operation	20
Incorrect HA status is displayed during a takeover or giveback operation ...	20
Partner disk state is incorrectly displayed as broken	21
Cannot specify the management IP address of the partner when adding an HA pair	21
System Manager cannot detect storage systems failure during giveback	21
Networking issues	22
Networking limitations	22
Network configuration checker reports a configuration mismatch	22
Network configuration checker does not verify all mismatches	22
Stale entries in the /etc/rc file and /etc/hosts file corrupt configuration settings	23
Network interface status mismatch is not detected	23
Cannot edit configuration settings for high-availability configurations	24

Cannot change the HA pair mode	24
Disabling dynamic DNS updates generates false alarms	24
Cannot make configuration changes when the high-availability pair is in takeover mode	25
Updating the /etc/rc file simultaneously changes the command sequence in the file	25
Modifying configuration settings when the Network Interfaces page is open introduces stale entries	25
System Manager operations might fail due to network issues	26
File access protocol issues	26
Inconsistent behavior while associating ACLs for shares with non- Unicode share name	26
Multiple NFS clients are displayed for an export with a single IPv6 client address	26
Data protection issues	27
SnapVault Relationships tab takes some time to load	27
New destination volume is created for a SnapVault relationship without verifying the eligibility of the source volume or qtree	27
Cannot create a SnapVault relationship if the source volume contains LUNs	27
Cannot set the tries value while creating a SnapVault schedule	28
Cannot create a transfer schedule by setting the SnapLock retention period on non-SnapLock volumes	28
SnapVault schedule creation fails while modifying the tries value	28
Cannot release a SnapVault relationship due to configuration mismatches	28
Cannot reset throttle to a default value after modifying it	29
Browser issues	29
Browser memory leak occurs if the application is run for more than a day	29
Graphs in Dashboard Window are not displayed on Chrome browser when you select a node in an HA pair	29
Unresponsive script error in System Manager	30
Cannot detect built-in Flash Player in Windows 8 and Windows Server 2012	30
Error reported if volume language is not UTF-8 compliant	30

Error reported if user comments are not UTF-8 compliant	31
Cannot launch System Manager	31
Other issues	32
Cannot delete UNIX groups	32
FC or FCoE service start fails with an incorrect error message	32
FlexCache volumes not supported	32
Default security style is set to UNIX for SAN volumes	32
Incorrect LDAP client configuration can cause SecD to abort	33
Cannot launch System Manager on Windows systems	33
Cannot display a job schedule that contains special characters	33
System Manager does not automatically display changes made to storage objects from the command-line interface	34
Home page information is not refreshed when SNMP service is down	34
System Manager is inaccessible over VPN	34
AutoSupport email address cannot be deleted if there is only one entry	35
Cannot delete a client from Exports window in System Manager	35
User name field is blank for each new login session	35
Copyright information	37
Trademark information	38
How to send your comments	39

System Manager 3.1 RC1 Release Notes

The release notes describe the fixed and known issues in this release of System Manager. System Manager 3.1 RC1 enables you to manage both storage systems running clustered Data ONTAP and storage systems running Data ONTAP operating in 7-Mode.

You can upgrade to the latest version of System Manager from 2.x or later versions. You must review the installation and upgrade information in the *Installation and Setup Guide* (formerly called the *Quick Start Guide*).

For information about supported Data ONTAP releases, see [support versions of Data ONTAP](#) on page 7.

Related information

[Documentation on the NetApp Support Site: support.netapp.com](http://support.netapp.com)

Understanding System Manager

System Manager is a graphical management interface that enables you to manage storage systems and storage objects (such as disks, volumes, and aggregates) and to perform common management tasks related to storage systems from a web browser.

System Manager enables you to perform many common tasks such as the following:

- Configure and manage storage objects, such as disks, aggregates, volumes, qtrees, and quotas.
- Configure protocols, such as CIFS and NFS, and provision file sharing.
- Configure protocols such as FC and iSCSI for block access.
- Verify and configure network configuration settings in the storage systems.
- Create vFiler units and configure CIFS.
- Set up and manage SnapMirror relationships and SnapVault relationships.
- Manage HA configurations and perform takeover and giveback operations.

Note: System Manager replaces FilerView as the tool to manage storage systems running Data ONTAP 8.1 or later.

Supported versions of Data ONTAP

You should be aware of the Data ONTAP versions that are supported by System Manager.

For storage systems running clustered Data ONTAP, System Manager supports the following versions:

- Data ONTAP 8.1.3 and 8.1.4

- Data ONTAP 8.2 and 8.2.1

For storage systems running Data ONTAP operating in 7-Mode, System Manager supports the following versions:

- Data ONTAP 7.3.7
- Data ONTAP 8.0.4 and 8.0.5
- Data ONTAP 8.1.3 and 8.1.4
- Data ONTAP 8.2 and 8.2.1

License requirements

System Manager is an unlicensed application and is free to download, install, and use. However, you require software licenses to enable certain services and features on your storage system, such as protocols and SnapMirror.

Many of the software licenses that you require for your storage system services and features are installed on the storage system at the factory.

Note: For HA pairs, you should install feature licenses on both the systems.

System requirements for System Manager

You must ensure that you have the required host system configuration, operating system, and browser to run the System Manager software. You must also have the necessary administrative privileges to access the software.

Your host system must meet the following minimum requirements:

- Pentium x86 processor
- 1 GB RAM
- 1 GB video display RAM
- 1 GB free disk space

If you are upgrading from an earlier version, you might require additional disk space for the existing log files.

- Wireless or Ethernet connection to the network
- 32-bit or 64-bit Windows or Linux operating system
- Adobe Flash Player 11.0 or later
- 32-bit or 64-bit Oracle Java Runtime Environment (JRE) 7
 - Installing 32-bit or 64-bit JRE depends on the operating system. If you are using a 32-bit Windows or Linux operating system, 32-bit JRE must be installed. Similarly, if you are using a 64-bit Windows or Linux operating system, a 64-bit JRE must be installed.
 - You can install 32-bit or 64-bit Oracle JRE 7 from www.java.com/en/download/manual.jsp.

Your Windows system must be running one of the following:

- Windows XP
- Windows Vista
- Windows 7
- Windows 8
- Windows Server 2003
- Windows Server 2008
- Windows Server 2008 R2
- Windows Server 2012

Your Linux system must be running one of the following:

- Red Hat Enterprise Linux 5 or 6
- SUSE Linux Enterprise Server 11

Your Linux system must have a graphical desktop environment, such as GNOME or KDE, installed.

Your web browser must be one of the following:

- Internet Explorer 9.0 or 10.0 (for Windows)

Note: Internet Explorer launched in the compatibility mode is not supported.

- Mozilla Firefox 23 or 24 (for both Windows and Linux)
- Google Chrome 28 or 29 (for Windows)

Note: You can run either a 32-bit browser or a 64-bit browser on a 64-bit operating system.

You should be aware of the following information:

- You should use a resolution of 1280 x 1024 pixels for optimal viewing.

Note: You must ensure that the screen width does not exceed 2000 pixels.

- You must ensure that the web browser is not in offline mode.

Note: For storage systems running Data ONTAP 8.2 or later operating in 7-Mode, you must enable HTTP by using the `httpd.admin.ssl.enable` option.

For information about the supported Data ONTAP versions, see [Supported versions of Data ONTAP](#) on page 7.

For the latest information about currently supported systems, see the Interoperability Matrix.

Related information

[Interoperability Matrix: support.netapp.com/NOW/products/interoperability](http://support.netapp.com/NOW/products/interoperability)

User interface enhancements

System Manager 3.1 RC1 includes an enhancement to support Data ONTAP operating in 7-Mode.

Array LUNs For Data ONTAP 8.2.1, you can install the V_StorageAttach license to add array LUNs to non-root aggregates.

Fixed issues

Some of the known issues in previous releases of System Manager are fixed in this release.

Network Interface page stops responding if the `/etc/rc` file does not contain standard characters

If the `/etc/rc` file contains nonstandard characters that have an ASCII value greater than 127, the Network Interface page stops responding.

For more information, see Bug ID 684875 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

Reverse resynchronization fails when a SnapMirror relationship is created using the system IP address

If you create a SnapMirror relationship using the source system's IP address instead of the system name, reverse resynchronization from the destination system fails. The issue occurs because System Manager cannot process the IP address of the system.

For more information, see Bug ID 685246 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

Cannot modify SnapLock retention periods simultaneously

In the Edit Volume dialog box, if you modify the maximum, minimum, and default SnapLock retention periods simultaneously, setting these values might fail.

Incorrect value displayed for volume security style in the Edit Volume window

An incorrect value is displayed for volume security style in the Edit Volume window if the volume name contains the terms `ntfs` or `mixed`.

For example, if the volume name is `vol_ntfs` with the security style set to `unix`, the security style value is displayed as `ntfs` in the Edit Volume window.

For more information, see Bug ID 723426 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](https://support.netapp.com/NOW/cgi-bin/bol)

Incorrect Snapshot copy timestamp displayed if daylight saving time is activated

If you are viewing Snapshot copies in System Manager when daylight saving time (DST) is activated in the storage system, an incorrect timestamp is displayed for the Snapshot copies.

For more information, see Bug ID 691281 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](https://support.netapp.com/NOW/cgi-bin/bol)

Volumes window displays incorrect Snapshot information

System Manager displays incorrect information about the used and available Snapshot reserve space for the selected volume in the Space Allocation tab of the Volumes window.

Configuring network interfaces with static subnet routes generates false alarms

The network configuration checker generates a false alarm when the network interfaces are configured using static subnet routes.

Following are some examples of the command syntax that are valid and invalid.

For example, if you enter the IPv4 command as `route add inet net 192.168.3.0/24 192.168.1.1 1`, a false alarm is generated because the command is invalid.

If you enter the same command using one of the following syntaxes, a false alarm is not generated because the command is valid:

- `route add inet net 192.168.3.0&255.255.255.0 192.168.1.1 1`
- `route add inet net 192.168.3.0 prefix 255.255.255.0 192.168.1.1 1`
- `route add inet net 192.168.3.0 netmask 255.255.255.0 192.168.1.1 1`

Similarly, if you enter the `inet6` command as `route add inet6 net 9ffe::/64 6ffe::1 1`, a false alarm is generated because the command is invalid. If you enter the same using this syntax, `route add inet6 net 9ffe:: prefix 64 6ffe::1 1`, false alarms are not generated.

For more information, see Bug ID 647773 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

System Manager does not reflect the storage system time if daylight saving time is activated

When you view events, jobs, system health, licenses and so on, in the respective pages in System Manager, the **Time Stamp** field might show a time difference of one hour from the storage system time. This occurs if daylight saving time (DST) is activated.

Cannot create an aggregate from the Disks page for Data ONTAP-v storage systems

System Manager does not allow you to create an aggregate with RAID0 option from the Disks page, although the Data ONTAP-v storage system is configured for RAID0.

Known issues with Data ONTAP

Some unexpected and potentially undesired behaviors in Data ONTAP are known to affect functionality in this release of System Manager.

Data becomes unavailable if MTU size is not specified in the `/etc/rc` file

When System Manager is used to manage storage systems running Data ONTAP versions earlier than 8.1.3 and the Network Interfaces page is opened or when the Network Configuration Checker is run, the storage system might panic if the MTU size is not specified, resulting in data unavailability.

Usually, for these Data ONTAP versions, data is served even if the MTU size is not specified in the `/etc/rc` file.

Workaround

Edit the `/etc/rc` file from the command-line interface and ensure that the MTU size is specified.

Incorrect error message is displayed when disabling thin provisioning in LUNs

When you disable thin provisioning for a LUN in storage systems running Data ONTAP 7.3.x and 8.0.x, and if there is insufficient space in the containing aggregate, the following error message is displayed: `Unknown error: 10008`.

Workaround

None.

Cannot change or remove the vFiler unit IP address

When you try to remove or change the IP address of a vFiler unit on storage systems running Data ONTAP 7.3.x, an error message is displayed and the operation fails.

Workaround

Remove or change the IP address of the vFiler unit from the command-line interface.

Known issues and limitations in System Manager

You should be aware of the known issues, limitations, and workarounds for each of the System Manager features so that you can use the product more effectively.

For more information about an individual bug, see the bug ID in Bugs Online on the NetApp Support Site.

Note: Currently Bugs Online does not display fixed-in version information for System Manager.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

Upgrade or installation issues

You should familiarize yourself with the upgrade or installation issues in this release.

System Manager installation fails with an error message

While installing System Manager on Windows, the installation fails with the following error message: `Error opening file for writing`. This issue occurs because the Jetty web server and browsers take a long time to shut down and do not allow you to delete the files because they are locked.

Workaround

Close the browsers manually and ensure that the Jetty web server is also terminated before performing the installation.

Java script error reported while upgrading System Manager

While upgrading to the latest version of System Manager, a Java script error is displayed if there are any Jetty processes running in the background or if any application is accessing the port that is used by System Manager.

Workaround

Close all browser windows and tabs before upgrading to System Manager.

Licensing issues

You should familiarize yourself with the issues related to the licensing feature in this release.

Cannot display the license grace period

For storage system running Data ONTAP 8.2 operating in 7-Mode, System Manager does not display the license grace period.

Workaround

Use the command-line interface to view the license grace period.

Storage resource management issues

You should familiarize yourself with the storage resource management issues in this release.

Resizing a LUN might result in data loss

While editing a LUN, if you choose to resize it, your data might be truncated and you might lose data.

Workaround

Evaluate the changes before resizing the LUN.

LUN Clone field does not display any value

When you select a LUN in the LUN Management tab of the LUNs window, the details page does not display any value for the LUN Clone field.

Workaround

None.

SSD disks cannot be added as cache disks from the Disks window

System Manager does not allow you to add SSD disks to an aggregate as cache disks from the Disks window.

Workaround

Use the Edit Aggregate dialog box in the Aggregate window to add SSD disks as cache disks.

System Manager does not perform disk size validation during RAID4 to RAID-DP conversion

In the Edit Aggregate dialog box, when you change the RAID type of an aggregate from RAID4 to RAID-DP, Data ONTAP selects an appropriate disk for the dual-parity disk in a RAID group.

However, System Manager does not perform any disk size validation when you change the RAID type.

Workaround

None.

Spare disk is downsized if the parity disk of a SyncMirror pool is smaller than the spare disk

When you replace a disk in a SyncMirror pool by using the Edit Aggregate dialog box, no warning message is displayed if you select a spare disk that is larger in size than any of the parity disks within the RAID group.

You must be aware of this scenario because this can result in the permanent downsizing of the spare disk to the largest existing parity disk size.

Workaround

None.

Delay in populating the Flash Cache read workload graph

If you disable a Flash Cache module from a management tab in the System Manager application and then enable it from the same management tab, the Flash Cache Read Workload graph is populated only after (approximately) two minutes.

Workaround

None.

Storage Configuration wizard does not validate disk sizes

For storage systems running Data ONTAP operating in 7-Mode, the Storage Configuration wizard does not validate the disk sizes when creating an aggregate.

While creating aggregates, the Storage Configuration wizard selects disks of mixed sizes if the storage system contains disks of different sizes. It is a best practice to create aggregates with disks of same size. You cannot use System Manager to add disks to aggregates with mixed disk sizes.

Workaround

None.

Cloning a LUN fails if the containing volume is created during the LUN creation operation

The LUN clone operation fails if you have created the LUN-containing volume during LUN creation in storage systems running Data ONTAP 8.1 operating in 7-Mode. The volume does not have sufficient space to accommodate the LUN clone and the LUN clone operation fails.

Workaround

Increase the size of the volume so that it can accommodate the size of the LUN clone that you create.

System Manager does not display online LUNs in an initiator group

If there are LUNs mapped to an initiator group, the LUNs are listed based on the initiators mapped to them. If an initiator is not present, System Manager cannot determine the online LUNs in the initiator group.

Workaround

None.

Incorrect number of spare disks displayed in the dashboard

The number of available spare disks displayed in the Disks section of the dashboard does not include zeroing disks. System Manager does not count zeroing disks as a spare disk.

Workaround

None.

Change in SSD RAID group size is not displayed for Data ONTAP 8.2

For storage systems running Data ONTAP 8.2, the SSD RAID group size is different from the HDD RAID group size. The Create Aggregate wizard and the Edit Aggregate dialog box do not display any change in the SSD RAID group size for storage systems running Data ONTAP 8.2.

The default size for SSD RAID group is 23. You must be aware of this information because adding more than 23 SSD disks might cause create or edit aggregate operations to fail.

Workaround

None.

Mixed RAID types are not supported

You cannot combine disks of different RAID types when creating an aggregate by using System Manager.

Workaround

None.

Incorrect spare disk count reported while mirroring aggregates with disks of different checksum types

While mirroring aggregates, an incorrect spare disk count is reported if the checksum types of the spare disks are different. As a result, the minimum number of hot spare disks is not maintained in the storage system.

Workaround

Ensure that the storage system contains the minimum number of hot spare disks of each checksum type.

Aggregates are created by selecting disks from the same carrier without a warning message

When you create aggregates for DS4486 shelves, System Manager might select disks from the same carrier without displaying a warning message.

It is a best practice to create aggregates by selecting disks from different carriers.

Workaround

Manually select the disks from the Disks page to create the aggregates.

FCAL disks are incorrectly displayed as SAS disks

In the Create Aggregate wizard, when you try to select disks for the aggregate, System Manager incorrectly displays FCAL disks as SAS disks.

Workaround

None.

For more information, see Bug ID 672624 in the Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

HA pairs issues

You should familiarize yourself with issues related to HA pairs in this release.

HA Configuration window displays timed-out error message during a giveback operation

If a giveback operation fails for an HA pair, System Manager does not detect these failures and the giveback operation status is incorrectly displayed as in progress. A `Giveback in progress` message is displayed and the operation might stop with a timed-out error message.

This issue occurs when the giveback response time exceeds the timeout value, or if the operation has failed.

Workaround

1. Refresh the HA Configuration window.
The giveback status shows success when the operation is completed.
2. If refreshing the window fails again with an error message, run the `storage failover giveback` command from the command-line interface (CLI) to start the giveback operation.

Incorrect HA status is displayed during a takeover or giveback operation

When you perform a takeover or a giveback operation for an HA pair, the HA Configuration window might display the HA status as `Error` instead of `Fai lover` for the failed node. The HA status is displayed as `Error` when System Manager cannot retrieve the HA status.

Workaround

1. Refresh the HA Configuration window to view the updated HA status.
2. If refreshing the window fails, run the `cf status` command from the command-line interface (CLI) to view the HA status.

For more information, see Bug ID 604647 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](https://support.netapp.com/NOW/cgi-bin/bol)

Partner disk state is incorrectly displayed as broken

System Manager 2.1 and later versions incorrectly display the partner disks state in HA configuration as Broken for storage systems running Data ONTAP 8.1. This issue occurs due to an API error.

Workaround

Use the command-line interface (CLI) to check the correct disk state.

You can also upgrade your storage system to Data ONTAP 8.1.1 and later releases.

For more information, see Bug ID 725403 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

Cannot specify the management IP address of the partner when adding an HA pair

When adding an HA pair, System Manager automatically discovers the IP address of the partner node and adds it. Management of the partner node might fail if the automatically discovered IP address is not a management IP address.

Workaround

Specify the management IP address of the partner against the fully qualified domain name in the hosts file of the system in which you have installed System Manager.

For more information, see Bug ID 547278 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

System Manager cannot detect storage systems failure during giveback

If a storage system fails during a giveback operation, System Manager does not detect it.

Workaround

None.

Networking issues

You should familiarize yourself with the networking issues in this release.

Networking limitations

You should be aware of certain networking limitations when you use System Manager.

In System Manager, you cannot perform the following network configurations:

- Change the configuration settings if the interfaces or routes that are configured in the active configuration are missing from the `/etc/rc` file.
- Delete a virtual LAN (VLAN).
- Delete an interface group.
- Add or remove trunks from an interface group.
- Edit the configuration for the interface that System Manager uses to manage the system.

If the order of the `/etc/rc` file structure is modified, System Manager displays a failure message. For more information about the `/etc/rc` file structure, see the *OnCommand System Manager Help For 7-Mode*.

Network configuration checker reports a configuration mismatch

When there is an unused VLAN, the network configuration checker tool in System Manager falsely reports a configuration mismatch because the tool does not check for the unused VLAN.

Workaround

Ignore the false report if the VLAN is unused.

Network configuration checker does not verify all mismatches

The network configuration checker tool in System Manager compares the active and persistent configuration values and the command sequence of some network configuration settings in the `/etc/rc` file. However, the network configuration checker tool does not verify all the parameters of the `ifconfig` command.

Only the following System Manager induced mismatches and errors are verified:

- `ifconfig` status
- `ifconfig` media type
- Truncation of characters in the `/etc/rc` and `/etc/hosts` files

For example, consider the command `ifconfig e0a hostname -e0a mediatype ato flocontrol full netmask 255.255.0.0 mtusize 1500`. In this example, the character “w”

is missing in the `flow control` option and “u” is missing in the value `auto` for the `media type` option. The network configuration checker tool detects this statement as a mismatched entry.

The tool detects corruption in the network commands, such as `ifconfig`, `ifgrp`, `route`, and `vlan`, and their corresponding arguments. However, if the corruption is in the argument values of the commands, the tool does not detect the corruption.

For more information, see Bug ID 690581 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](https://support.netapp.com/NOW/cgi-bin/bol)

Stale entries in the `/etc/rc` file and `/etc/hosts` file corrupt configuration settings

Stale entries in the `/etc/rc` file or the `/etc/hosts` file cause misconfigurations. The Network configuration checker does not detect these stale entries that corrupt the configuration settings of the storage system on reboot.

Workaround

Use the command-line interface to remove the stale entries from the files.

For more information, see Bug ID 642024 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](https://support.netapp.com/NOW/cgi-bin/bol)

Network interface status mismatch is not detected

If there is a mismatch in the network interface status between the `/etc/rc` file and the active configuration settings of storage systems running Data ONTAP 7.3.x, the Network Configuration Checker might not detect these configuration changes on the storage systems.

Workaround

None.

For more information, see Bug ID 644225 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](https://support.netapp.com/NOW/cgi-bin/bol)

Cannot edit configuration settings for high-availability configurations

If there are errors in the high-availability configuration, System Manager disables the network configuration. You cannot edit the configuration settings because System Manager interprets the node to be in a taken over state.

Workaround

Use the command-line interface to correct the configuration errors in the HA pair.

For more information, see Bug ID 647748 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

Cannot change the HA pair mode

When you change the HA pair mode to Standby or Dedicated, the primary IP address and partner interface details are not deleted for the respective modes, and the HA pair continues to operate in the previous mode.

Workaround

Delete the IP address and partner interface details manually from the Edit Network Interfaces dialog box.

For more information, see Bug ID 643428 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

Disabling dynamic DNS updates generates false alarms

The Network Configuration Checker generates a false alarm when dynamic DNS updates are disabled for IP addresses.

Workaround

Prefix the IP address with `no_ddns`, as follows:

- `ifconfig e0a no_ddns host_name -e0a`
- `ifconfig e0a alias no_ddns IP_address`

Cannot make configuration changes when the high-availability pair is in takeover mode

When a node is in takeover mode and if you disable the Vif, any configuration change you make is not updated in the `/etc/rc` file and the status of the Vif is still disabled.

System Manager does not display the status of the local network interface and its partner interface. Therefore, when a partner interface is down and the local network interface takes over and serves data, the status of the local network interface is enabled-partner up. If you attempt to disable the local network interface status, the status on the system changes, but System Manager still displays the network interface status as enabled. Therefore, you cannot enable the status of the local network interface.

Workaround

Use the command-line interface to enable the Vif.

For more information, see Bug ID 604739 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](https://support.netapp.com/NOW/cgi-bin/bol)

Updating the `/etc/rc` file simultaneously changes the command sequence in the file

If the `/etc/rc` file is simultaneously updated using more than one method such as the command-line interface as well as an external interface, and if the changes are made to the configuration settings using System Manager, the sequence of commands in the `/etc/rc` file is modified.

Workaround

None.

Modifying configuration settings when the Network Interfaces page is open introduces stale entries

If the active configuration settings of the storage system are modified when the Network Interfaces page is open, System Manager does not refresh the page automatically, and stale entries are written to the `/etc/rc` file.

Workaround

None.

System Manager operations might fail due to network issues

If System Manager is running on a network that has latency issues, data packets might be dropped and System Manager operations might fail.

Workaround

Refresh your browser and try the operation again.

For more information, see Bug ID 484647 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

File access protocol issues

If your storage systems provide CIFS or NFS client services, you should familiarize yourself with the file access protocol issues in this release.

Inconsistent behavior while associating ACLs for shares with non-Unicode share name

For storage systems running Data ONTAP 8.0 or earlier, System Manager behaves inconsistently if you try to edit the share permissions for a share name that contains a non-Unicode character. Sometimes, ACLs are not associated with the share.

Workaround

Edit the share permissions by entering the following command from the command-line interface:

```
cifs access share_name {user|group} rights
```

Multiple NFS clients are displayed for an export with a single IPv6 client address

The Exports window in System Manager displays multiple NFS clients even though the volume has only one IPv6 client address.

The issue occurs when an administration host IPv6 address is not enclosed in square brackets ([]) in the 7-Mode setup command. System Manager displays eight NFS clients for the eight octet IPv6 address for new volumes if the IP address is not enclosed in brackets.

Workaround

Ensure that you enclose the administration host IP address in brackets if the address is in IPv6 format in the `/etc/exports` file.

Data protection issues

If you are using the SnapMirror feature or the vault feature, you should familiarize yourself with the data protection issues in this release.

SnapVault Relationships tab takes some time to load

When there are a large number of interface groups or virtual local area networks (VLANs) on the controller, the SnapVault Relationships tab takes some time to load and display information.

When a large number of interface groups or VLANs are created on the controller, System Manager retrieves information about these entities. Therefore, SnapVault Relationships tab might take some time to load. For example, for a storage controller that has four or five interface groups or VLANs, the SnapVault Relationships tab takes approximately 8 seconds to load.

Workaround

If there are a large number of interface groups or VLANs present, there is no viable workaround other than waiting until System Manager finishes retrieving information.

New destination volume is created for a SnapVault relationship without verifying the eligibility of the source volume or qtree

While creating a SnapVault relationship, System Manager does not verify if the source volume or qtree is eligible for a SnapVault relationship and creates a new destination volume. However, the SnapVault relationship creation fails.

A source volume is not eligible for a SnapVault relationship if it contains LUNs or if it is already a destination in a SnapVault relationship.

System Manager does not display a warning message when a source volume that is already in a SnapVault relationship is used to create a new destination volume.

Workaround

Use the new destination volume to establish another SnapVault relationship, or delete it.

Cannot create a SnapVault relationship if the source volume contains LUNs

When you create a SnapVault relationship between a source volume containing LUNs and a destination qtree, System Manager does not detect the presence of LUNs and the creation fails.

Workaround

Ensure that the source volume from which you want to back up data does not contain LUNs.

Cannot set the tries value while creating a SnapVault schedule

For storage systems running Data ONTAP versions 8.0 through 8.0.3, 8.1, and 8.1.1, although you can create a SnapVault schedule, you cannot set the tries value to change the number of attempts to create a Snapshot copy.

Workaround

None.

Cannot create a transfer schedule by setting the SnapLock retention period on non-SnapLock volumes

For storage systems running Data ONTAP 8.1 operating in 7-Mode, when you create a SnapVault transfer schedule by setting the SnapLock retention period for a non SnapLock volume, the schedule creation fails.

Workaround

Ensure that you set the SnapLock retention period only on SnapLock volumes.

SnapVault schedule creation fails while modifying the tries value

For storage system running Data ONTAP 8.0 through 8.0.3, 8.1, and 8.1.1, if you modify the tries value (number of attempts to create a Snapshot copy) when you create or modify a SnapVault schedule, the schedule creation fails.

Workaround

None.

Cannot release a SnapVault relationship due to configuration mismatches

If there are configuration mismatches in a SnapVault relationship, releasing the SnapVault relationship from the source system or destination system fails.

Workaround

Use the `snapvault-destinations` command to determine if the destination system can be released.

Cannot reset throttle to a default value after modifying it

If you do not set the throttle value while creating a SnapVault relationship, the default value of 4 TBps is set. If you change this default throttle value, you cannot reset it to its default value; however, you can set a value between 0 through 2 TBps.

If you modify the configuration settings of this SnapVault relationship, such as the tries value, the throttle value is reset to an unlimited bandwidth without any warning message.

Workaround

None.

Browser issues

You should familiarize yourself with the browser issues in this release of System Manager.

Browser memory leak occurs if the application is run for more than a day

System Manager experiences browser memory leaks if the application is continuously running for more than a day. The background panes of the application are not displayed correctly and appear black. However, the active window is displayed correctly.

Workaround

Close and reopen the browser to correctly display all the windows in System Manager.

Graphs in Dashboard Window are not displayed on Chrome browser when you select a node in an HA pair

The graphs in the Dashboard window are not displayed when you select a node in an HA pair from the left navigation pane. This issue occurs only in the Google Chrome browser running on Windows 7 and Windows 8 platforms.

Workaround

To display graphs in the Dashboard window, switch between tabs or browser windows. The graphs are loaded successfully.

Unresponsive script error in System Manager

System Manager displays an unresponsive script error when the response time exceeds the browser timeout value. System Manager displays this error when large amount of data is searched and loaded, and the error is displayed because of a browser limitation.

Workaround

Click **Continue** and wait for the browser to load.

Cannot detect built-in Flash Player in Windows 8 and Windows Server 2012

System Manager cannot detect the built-in Flash Player in Internet Explorer.

Adobe Flash Player 11.0 or later must be installed on your host system to monitor the health and performance of storage systems by using the Dashboard window.

If you are using Internet Explorer as your browser and when you open the Dashboard window, System Manager prompts you to install the Flash Player if it is not installed already. When you try to install the Flash Player, System Manager displays an error message specifying that the Flash Player is already installed.

Workaround

Install the Flash Player using another browser.

Error reported if volume language is not UTF-8 compliant

While creating shares, when you browse for folders or files, an error is reported if the folders or files contain special characters (such as umlaut).

The XML errors are specific to browsers. Internet Explorer displays an XML parse error. Mozilla Firefox and Google Chrome cannot display the special characters and display other errors.

Workaround

Use the command-line interface and change the volume language from *lang_name* to *lang_name.UTF-8*. For example, if the volume language setting is German (de), change the language settings to de.UTF-8.

For more information, see Bug ID 607172 in Bugs Online.

Related information

Bugs Online: support.netapp.com/NOW/cgi-bin/bol

Error reported if user comments are not UTF-8 compliant

When System Manager is opened in Internet Explorer version 8 or 9, and if user comments contain special characters (such as umlaut), an XML parse error is reported.

Workaround

Ensure that the comments entered are UTF-8 compliant.

For more information, see Bug ID 596537 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

Cannot launch System Manager

If the file path of the browser that is used to launch System Manager is incorrectly specified in the configuration file, when you try to launch System Manager an error message is displayed requesting you to verify the browser path.

Workaround for Windows

Perform the following steps to modify the browser path:

1. Navigate to the user preference directory that contains the System Manager configuration file:
 - For systems running Windows Vista or later, navigate to `c:\Users\user_name\NetApp\SystemManager`
 - For systems running Windows XP, navigate to `c:\Documents and Settings\user_name\NetApp\SystemManager`
2. Open the `SystemManager.config` file in a text editor and modify the browser path specified in the `<browser>` `</browser>` tag.

Workaround for Linux

Perform the following steps to modify the browser path:

1. Navigate to `/root/NetApp/SystemManager/` that contains the System Manager configuration file.
2. Open the `SystemManager.config` file in a text editor and modify the browser path specified in the `<browser>` `</browser>` tag.

Other issues

There are certain issues you should be aware of when you use System Manager.

Cannot delete UNIX groups

You cannot delete UNIX groups by using System Manager for storage systems running Data ONTAP versions earlier than 8.1.

Workaround

Use the command-line interface (CLI) and run the `cifs access -delete` command to delete UNIX groups. For example:

```
cifs access -delete HOME -g ip3poe7
```

FC or FCoE service start fails with an incorrect error message

System Manager displays an incorrect error message when you start the FC or FCoE service without an FC adapter present in the target storage system.

The following error message is displayed: Data ONTAP API Failed :Cluster interconnect has never been up. If clustering has just been licensed a reboot is required to enable the cluster interconnect, or the cluster cables could be unplugged. Please correct before starting fcp (Error: 9073).

Workaround

None.

FlexCache volumes not supported

You cannot manage FlexCache volumes by using System Manager.

Workaround

None.

Default security style is set to UNIX for SAN volumes

System Manager sets the default security style of SAN volumes to UNIX while creating volumes even though the default security style option `wafl.default_security_style` is set to `ntfs`.

Workaround

None.

Incorrect LDAP client configuration can cause SecD to abort

System Manager allows you to create an LDAP client configuration by specifying the Active Directory domain name. However, if you do not specify the IP address of the preferred Active Directory server or you specify an incorrect IP address, the LDAP client configuration becomes invalid, causing SecD to abort and go into a restart loop.

System Manager does not display any warning message when you create an invalid LDAP client configuration.

Workaround

Use the command-line interface to delete the LDAP client configuration that contains the entry with an invalid IP address or no IP address. Additionally, provide the correct IP address for the preferred Active Directory server when creating the LDAP client configuration along with the Active Directory domain name.

Cannot launch System Manager on Windows systems

When you try to launch System Manager on Windows systems, the application does not open and the following error message is displayed: `Error while starting Jetty`
`java.net.SocketException: denied: listen.`

Workaround

Add the following values for a new Windows environment variable in the Advanced tab of the System Properties window:

Variable name: **_JAVA_OPTIONS**

Variable value: **-Djava.net.preferIPv4Stack=true**

Cannot display a job schedule that contains special characters

When you create a new job schedule with a name that includes the special characters the ampersand (&), less than symbol (<), and greater than symbol (>) from the command-line interface, System Manager does not display this schedule in the Schedules window.

Workaround

None.

System Manager does not automatically display changes made to storage objects from the command-line interface

If you modify a storage object from the command-line interface and if the storage object is also managed by the System Manager application, although the storage object is added to System Manager, the changes are not displayed in the application.

For example, in a volume that is added to System Manager, if you enable deduplication on the volume from the command-line interface, System Manager does not reflect these changes until you manually refresh the Volume page.

Workaround

Manually refresh the System Manager application page.

Home page information is not refreshed when SNMP service is down

The information in the Home page in System Manager is refreshed through SNMP. However, if the SNMP service is down or if an SNMP community is not configured, then System Manager does not refresh the list of storage systems in the Home page.

Workaround

You must add the storage system again.

System Manager is inaccessible over VPN

On a machine that has Java 7 and is running Windows 7 or Windows Server 2008, when you access System Manager through a virtual private network (VPN) connection, the following error message is displayed: Permission denied: connect.

Workaround

Install the hotfix from the Microsoft website at: support.microsoft.com/kb/2750841.

For more information, see Bug ID 626839 in Bugs Online.

Related information

Bugs Online: support.netapp.com/NOW/cgi-bin/bol

AutoSupport email address cannot be deleted if there is only one entry

If there is only one email address specified as the AutoSupport message recipient in the Edit AutoSupport Settings window, you cannot delete the entry through System Manager. Although the delete operation appears to be completed successfully, the email address is not deleted.

Workaround

Use the command-line interface to delete the email address.

Cannot delete a client from Exports window in System Manager

While deleting a client from the Exports window, the following error message is displayed: Data ONTAP API Failed :Error no valid name found with exports-hostname-info.

Workaround

In the Edit Export Rule window, select the client and click **Delete**.

For more information, see Bug ID 648612 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](http://support.netapp.com/NOW/cgi-bin/bol)

User name field is blank for each new login session

If the System Manager configuration file is corrupted, the user name field in the login screen is populated with a null value instead of the cached user name when a user attempts to log in. As a result, the user name must be manually entered for each login attempt.

Workaround for Windows

Navigate to the user preference directory and delete the `SystemManager.config` and `SystemManager.ks` files:

- For systems running Windows Vista or later, navigate to `c:\Users\user_name\NetApp\SystemManager` for the files.
- For systems running Windows XP, navigate to `c:\Documents and Settings\user_name\NetApp\SystemManager` for the files.

Workaround for Linux

Navigate to `/root/NetApp/SystemManager/` and delete the `SystemManager.config` and `SystemManager.ks` files.

For more information, see Bug ID 592472 in Bugs Online.

Related information

[Bugs Online: support.netapp.com/NOW/cgi-bin/bol](https://support.netapp.com/NOW/cgi-bin/bol)

Copyright information

Copyright © 1994–2013 NetApp, Inc. All rights reserved. Printed in the U.S.

No part of this document covered by copyright may be reproduced in any form or by any means—graphic, electronic, or mechanical, including photocopying, recording, taping, or storage in an electronic retrieval system—without prior written permission of the copyright owner.

Software derived from copyrighted NetApp material is subject to the following license and disclaimer:

THIS SOFTWARE IS PROVIDED BY NETAPP "AS IS" AND WITHOUT ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, WHICH ARE HEREBY DISCLAIMED. IN NO EVENT SHALL NETAPP BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

NetApp reserves the right to change any products described herein at any time, and without notice. NetApp assumes no responsibility or liability arising from the use of products described herein, except as expressly agreed to in writing by NetApp. The use or purchase of this product does not convey a license under any patent rights, trademark rights, or any other intellectual property rights of NetApp.

The product described in this manual may be protected by one or more U.S. patents, foreign patents, or pending applications.

RESTRICTED RIGHTS LEGEND: Use, duplication, or disclosure by the government is subject to restrictions as set forth in subparagraph (c)(1)(ii) of the Rights in Technical Data and Computer Software clause at DFARS 252.277-7103 (October 1988) and FAR 52-227-19 (June 1987).

Trademark information

NetApp, the NetApp logo, Network Appliance, the Network Appliance logo, Akorri, ApplianceWatch, ASUP, AutoSupport, BalancePoint, BalancePoint Predictor, Bycast, Campaign Express, ComplianceClock, Cryptainer, CryptoShred, CyberSnap, Data Center Fitness, Data ONTAP, DataFabric, DataFort, Decru, Decru DataFort, DenseStak, Engenio, Engenio logo, E-Stack, ExpressPod, FAServer, FastStak, FilerView, Flash Accel, Flash Cache, Flash Pool, FlashRay, FlexCache, FlexClone, FlexPod, FlexScale, FlexShare, FlexSuite, FlexVol, FPolicy, GetSuccessful, gFiler, Go further, faster, Imagine Virtually Anything, Lifetime Key Management, LockVault, Mars, Manage ONTAP, MetroCluster, MultiStore, NearStore, NetCache, NOW (NetApp on the Web), Onaro, OnCommand, ONTAPI, OpenKey, PerformanceStak, RAID-DP, ReplicatorX, SANscreen, SANshare, SANtricity, SecureAdmin, SecureShare, Select, Service Builder, Shadow Tape, Simplicity, Simulate ONTAP, SnapCopy, Snap Creator, SnapDirector, SnapDrive, SnapFilter, SnapIntegrator, SnapLock, SnapManager, SnapMigrator, SnapMirror, SnapMover, SnapProtect, SnapRestore, Snapshot, SnapSuite, SnapValidator, SnapVault, StorageGRID, StoreVault, the StoreVault logo, SyncMirror, Tech OnTap, The evolution of storage, Topio, VelocityStak, vFiler, VFM, Virtual File Manager, VPolicy, WAFL, Web Filer, and XBB are trademarks or registered trademarks of NetApp, Inc. in the United States, other countries, or both.

IBM, the IBM logo, and ibm.com are trademarks or registered trademarks of International Business Machines Corporation in the United States, other countries, or both. A complete and current list of other IBM trademarks is available on the web at www.ibm.com/legal/copytrade.shtml.

Apple is a registered trademark and QuickTime is a trademark of Apple, Inc. in the United States and/or other countries. Microsoft is a registered trademark and Windows Media is a trademark of Microsoft Corporation in the United States and/or other countries. RealAudio, RealNetworks, RealPlayer, RealSystem, RealText, and RealVideo are registered trademarks and RealMedia, RealProxy, and SureStream are trademarks of RealNetworks, Inc. in the United States and/or other countries.

All other brands or products are trademarks or registered trademarks of their respective holders and should be treated as such.

NetApp, Inc. is a licensee of the CompactFlash and CF Logo trademarks.

NetApp, Inc. NetCache is certified RealSystem compatible.

How to send your comments

You can help us to improve the quality of our documentation by sending us your feedback.

Your feedback is important in helping us to provide the most accurate and high-quality information. If you have suggestions for improving this document, send us your comments by email to doccomments@netapp.com. To help us direct your comments to the correct division, include in the subject line the product name, version, and operating system.

You can also contact us in the following ways:

- NetApp, Inc., 495 East Java Drive, Sunnyvale, CA 94089 U.S.
- Telephone: +1 (408) 822-6000
- Fax: +1 (408) 822-4501
- Support telephone: +1 (888) 463-8277